



City of Phoenix

Project No.
ST83120034

August 2009

Project Personnel

City of Phoenix

Engineering Supervisor
Syd Anderson, P.E.

Contractor

Knochel Bros. Contracting
Project Manager
David Brown

For More Information

If you have a comment, question or complaint about any aspect of the construction activity, please contact InRoads Info, Inc., your public information contact by dialing the

Construction Hotline



(480) 281-1506

Contractor's Work Hours

The contractor's work hours will be 6:00 am to 4:00 pm, Monday through Friday. Some weekend work may occur.

This publication can be made available in braille, large print, audiotape, or cassette tape upon request. Contact the Street Transportation Department at 602-262-6284 if you would like any of these services. The TTY phone number is 602-256-4286.

Pre-Construction Notification

City of Phoenix

23rd Avenue and Roeser Road
Detention Basin Improvement Project

Project Description

The City of Phoenix has contracted with Knochel Bros. Contracting to construct a new multi-use field / detention basin located on the northeast corner of 23rd Avenue and Roeser Road north of Lindo Park.

Detention basin improvements include: installation of a new storm drain pipe and inlet structure that will connect to the newly constructed storm drain system in Roeser Road located on the west side of the new basin; earthwork including clearing and grubbing of existing vegetation located within the basin site, excavation, placement of fill material, and grading and shaping of the new detention basin.

Multi-use field improvements include: installation of an access pathway connecting the new multi-use field to Lindo Park and Roeser Road; and installation of landscape materials, including new lighting, grass, and trees throughout the entire detention basin / multi-use field area.

Project Schedule

The contract allows 120 days for construction of the Multi-Use Field / Detention Basin Improvement Project. Pre construction work will begin on Monday, August 10, 2009. This work includes staking the project limits, and clearing and grubbing the existing plant materials. Heavy excavation work will begin in mid August and take approximately 30 days to complete. Upon completion of the heavy earth work, the contractor will fine grade the new basin, and begin installation of the new storm drain pipe and inlet structure. This work will take approximately 30 days to complete, and will be followed by installation of the concrete pathway, lighting, grass and trees. The overall estimated project time of completion is mid December 2009.

Traffic Restrictions

Traffic restrictions will not occur during this work. However, during the first 30 days of construction, heavy construction truck traffic will occur west of the multi-use field / detention basin site on Roeser Road between 23rd Avenue and 27th Avenue. Please watch for additional truck traffic during this time.

We realize that this project will cause some inconveniences, however the long-term drainage and multi-use field improvements should greatly benefit you and your neighbors.



Thank you for
your understanding
and cooperation!